



- Notes:
1. Plate ice making capacity: 90T/day
  2. Nominal ice storage capacity: 50T, theoretical capacity: 55T
  3. Horizontal ice delivery screw: 16T/hr
  4. Pneumatic ice delivery system, 6T/hr, delivery distance 80m, vertical height about 4m;
  5. The client should prepare well the rainproof work for the equipments.
  6. All water pipelines, power lines, refrigeration pipelines and air source should be connected to our designated ports by the customer on site.
  7. All the steel structure foundation should be prepared well by the customer, and checked with the qualified design institute;
  8. Supply scope is subject to the Sales Contract;

Itemref	Quantity	Title/Name, designation, material, dimension etc	Article No./Reference		
Designed by	Checked by	Approved by - date	Filename	Date	Scale
			ICE PLANT LAYOUT		
			CF900ET-6+IS-50+ID-6A	Edition	Sheet 1/?